P.O. Box 176, Savona, BC, Canada V0K 2J0
Phone: (250) 373-2424 Fax: (250) 373-2323
Website: savonaequipment.com
Email: sales@savonaequipment.com
Located just 20 minutes west of Kamloops, BC

Ross 100 Cement Batch Plant

[Inventory ID #124868]

- Ross 100 Cement Batch Plant.
  - Consisting of:
    - Batch Plant:
      - 27 yd³ product aggregate bin.
        - With air operated clam shell dump gates.
      - 4 yard aggregate batch weigh hopper.
        - With 24 in. wide x 12 ft. long discharge conveyor.
      - 890 ft³ (44.5 ton) cement silo.
        - With twin 6 in. diameter x 12 ft. long discharge auger feeding seperate cement weigh hopper.
      - 24 in. wide x 40 ft. long final product covered discharge conveyor.
      - Also comes with:
        - Digital display for both aggregate and cement scale.
        - Ingersoll-Rand T30 two stage air compressor.
          - Belt drive by a 10 hp, 208-230/460V electric motor.
        - Electrical starter panel.
        - Breaker panel.
      - All bins and hoppers equipped with pneumatic material vibrators.
      - Mounted on a 40 ft. single axle, dual wheel chassis with fifth wheel pin.
    - 40 ft. Additive Storage Container and Operator Station:
      - 7 additive metering cylinders.
        - Various sizes from 4 in. - 10 in. diamater x 2 ft. - 2.5 ft. long.
      - 1 additive metering cylinder.
        - 12 in. diameter x 4 ft. long.
      - All come with pneumatic controls.
      - Sight glass with level gauge.
      - 3 Ingersoll-Rand ¾ in. air operated diaphragm pumps.

- 1 Ingersoll-Rand ½ in. air operated diaphragm pump.
- 2 vertical poly storage tanks.
    - 4 ft. diameter x 6 ft. tall.
        - 2500 litre capacity.
- 2 vertical poly storage tanks.
    - 3 ft. diameter x 7 ft. tall.
        - 1500 litre capacity.
- 1 water metering valve.
    - Size: 1½ in.

- Electrical Container:
    - Hammond 75 kVA Transformer.
        - 600V - 208/120V.
    - 1 - Cutler Hammer 200 amp fused disconnect.
    - 2 - Cutler Hammer 100 amp fused disconnect.
    - 1 - Siemens 60 amp fused disconnect.
    - 1 - Cutler Hammer 225 A, 42 circuit panel board.
        - Complete with:
            - 1 - 60 A, 3 pole breaker.
            - 1 - 50 A, 2 pole breaker.
            - 1 - 30 A, 2 pole breaker.
            - 1 - 15 A, 2 pole breaker.
            - 4 - 15 A, 1 pole breaker,
        - Internal lighting.
- Also included with plant:
    - 2 - 1984 Peterbilt 10 yard cement trucks.
        - Engine: Caterpillar 3306.
        - Transmission: Road Ranger 7 speed.
        - Tandem rear axle with booster axle.
        - Front tires: Oversize - 425/65R22.5.
        - Rear tires: 11R22.5.
        - Mileage:
            - Truck 1: 239,737 miles.
            - Truck 2: 252,717 miles.
    - 8 World Block concrete lock block molds.
        - 30 in. x 20 in. x 60 in.
            - With textured inserts.
    - Taper block mold.
    - Half block mold.

Please contact us for more information.